

Dual Enclosure Liquid Cooling (DELC) Chiller-less Data Centers with Liquid Cooled Servers To Enable Significant Data Center Energy Savings

Dr. Madhu Iyengar, Senior Engineer, STG Advanced Thermal Lab December 13th 2011, Energy Efficiency HPC Working Group

Madhusudan Iyengar, Milnes David, Vinod Kamath, David Graybill, Bejoy Kochuparambil, Robert Simons and Roger Schmidt. IBM System and Technology Group (STG)

Timothy Chainer (PI), Michael Gaynes, Pritish Parida, Mark Schultz, Arun Sharma, and Hien Dang. IBM Research Division

IBM Acknowledgements: Pok Site & Facilities/G&E (Donato Caferra, Sal Rosato, Joe Caricari, Tony "D", Yun Lau, Chris), Pat Coico, James Steffes, Corey Vandeventer, Mark Steinke, Gerry Weber, Mike Ellsworth, James Whately, Brenda Horton, Yves Martin



Acknowledgements

This project was supported in part by the U.S. Department of Energy's Industrial Technologies Program under the American Recovery and Reinvestment Act of 2009, award no. DE-EE0002894. We thank the DOE Project Officer Debo Aichbhaumik, DOE Project Monitors Darin Toronjo and Chap Sapp and DOE HQ Contact Gideon Varga for their support throughout the project.

Traditional data center cooling infrastructure





Innovative data center design

- Eliminate chillers and room air-conditioning.
- Reject heat to ambient using server liquid cooling.
- Reduce refrigerant and make up water usage.





DOE outdoor loop layout (using a dry cooler to reject heat to the outdoor air)



IBM, December 13th 2011, Energy Efficiency HPC Working Group



Piping layout inside the lab



IBM, December 13th 2011, Energy Efficiency HPC Working Group



Water Cooling Unit (WCU) - Buffer unit





Programmable Logic Control (PLC)

- Collects power/thermal data from data center loop devices.
- Controls external pump, external fan, and three-way valve (winter).
- Allows Labview full control or uses embedded control algorithm for robust operation.
- Takes over control in case of "safety" events.
- Can be turned on and directly used in PLC mode.
- Provides learning for integrating commercial strength BMS with rack level operation.





Rack level cooling design

- Cool servers using warm water and air supply.
- Totally (100%) liquid cooled at rack level.
- Advanced thermal interfaces in key locations.



R. Schmidt, M. Iyengar, D. Porter, G. Weber, D. Graybill, and J. Steffes, 2010, "Open Side Car Heat Exchanger that Removes Entire Server Heat Load Without any Added Fan Power", Proceedings of the IEEE ITherm Conference, Las Vegas, June.

U.S. Patent 6,775,137, "Method and Apparatus for Combined Air and Liquid Cooling of Stacked Electronic Components," R.C. Chu, M.J. Ellsworth, Jr., E. Furey, R.R. Schmidt, and R.E. Simons



IBM System X 1U server - x3550M3



Air cooled server



Water cooled server with CPU and DIMM liquid cooling w/ 3 fans



Server liquid cooling components



11

Server liquid cooling sub-assemblies

Patent pending

Thermal chamber test for air/liquid cooled servers

| CASE A | CASE B |
|---|--|
| <u>"Cool" air cooled node</u> 25.3°C inlet air temperature Exerciser setting at 90% 12 fans running at 7242 rpm (avg.) System power = 395 W Fan power = 19.1 W CPU lid temps. = 65.3 °C, 74 °C DIMM temperatures = 35-46 °C 12 x 8 GB DIMMS | <u>"Hot" air cooled node</u> 35.4°C inlet air temperature Exerciser setting at 90% 12 fans running at 11978 rpm (avg.) System power = 423 W Fan power = 56.8 W CPU lid temps. = 68.9 ° C, 71.9 °C DIMM temperatures = 35-46 °C 12 x 8 GB DIMMS |

| ן ע |
|---|
| bled node temperature er temperature g at 90% t 5838 rpm (avg) 354 W W → 36.8°C, 35.9°C ures → 28-33 °C |
| |

Typical Poughkeepsie weather data (NREL)

14

Experimental data for 22 h test (August 2011)

Total data center cooling power is less than 3.5% of IT for a hot NY summer day

| Date Stamp | Time Stamp | Ave. outside air temp | Ave. IT Power | Ave. Cooling Power | Cooling power as % of IT | Ave. server inlet air temp | Ave. rack inlet water temp |
|------------|-------------|--------------------------|------------------|-----------------------|-----------------------------|----------------------------|-------------------------------|
| | | С | kW | kW | | С | С |
| 8/4/2011 | 4:00:30 PM | 28.1 | 13.43 | 0.440 | 3.28 | 38.1 | 36.3 |
| 8/4/2011 | 4:59:56 PM | 28.1 | 13.47 | 0.442 | 3.28 | 38.5 | 36.4 |
| 8/4/2011 | 6:00:22 PM | 27.9 | 13.50 | 0.441 | 3.27 | 38.6 | 36.4 |
| 8/4/2011 | 7:00:54 PM | 27.3 | 13.48 | 0.440 | 3.26 | 38.5 | 36.2 |
| 8/4/2011 | 8:01:25 PM | 26.3 | 13.43 | 0.433 | 3.23 | 38.2 | 35.8 |
| 8/4/2011 | 9:01:54 PM | 24.9 | 13.36 | 0.433 | 3.24 | 37.7 | 35.2 |
| 8/4/2011 | 10:02:17 PM | 23.2 | 13.22 | 0.438 | 3.31 | 36.9 | 34.2 |
| 8/4/2011 | 11:02:41 PM | 22.4 | 13.09 | 0.437 | 3.33 | 36.2 | 33.3 |
| 8/5/2011 | 12:03:04 AM | 21.7 | 12.99 | 0.439 | 3.38 | 35.5 | 32.6 |
| 8/5/2011 | 1:03:27 AM | 20.9 | 12.96 | 0.440 | 3.39 | 35.1 | 32.0 |
| 8/5/2011 | 2:03:49 AM | 20.2 | 12.88 | 0.443 | 3.44 | 34.6 | 31.2 |
| 8/5/2011 | 3:04:12 AM | 19.8 | 12.81 | 0.441 | 3.44 | 34.3 | 30.8 |
| 8/5/2011 | 4:04:34 AM | 19.4 | 12.77 | 0.442 | 3.46 | 34.0 | 30.4 |
| 8/5/2011 | 5:04:58 AM | 19.1 | 12.76 | 0.443 | 3.47 | 33.9 | 30.3 |
| 8/5/2011 | 6:05:24 AM | 19.0 | 12.76 | 0.448 | 3.51 | 33.8 | 30.4 |
| 8/5/2011 | 7:05:46 AM | 19.0 | 12.77 | 0.440 | 3.45 | 33.9 | 30.4 |
| 8/5/2011 | 8:06:10 AM | 20.8 | 12.79 | 0.437 | 3.41 | 34.3 | 31.1 |
| 8/5/2011 | 9:06:41 AM | 23.3 | 13.01 | 0.432 | 3.32 | 35.8 | 33.3 |
| 8/5/2011 | 10:07:10 AM | 25.0 | 13.21 | 0.432 | 3.27 | 37.2 | 35.0 |
| 8/5/2011 | 11:07:40 AM | 27.4 | 13.37 | 0.437 | 3.27 | 38.0 | 35.9 |
| 8/5/2011 | 12:08:12 PM | 29.1 | 13.48 | 0.449 | 3.33 | 38.6 | 36.6 |
| 8/5/2011 | 1:08:44 PM | 30.5 | 13.58 | 0.465 | 3.43 | 39.3 | 37.3 |
| 8/5/2011 | 1:55:08 PM | 31.0 | 13.58 | 0.477 | 3.51 | 39.5 | 37.6 |

Temperature data for 22 h test (August 2011)

Total data center cooling power is 3.5% of IT for a hot NY summer day

Power data for 22 h test

Cooling PUE data for 22 h test (August 2011)

Analyses for 9 US cities for a summer day

Energy and energy cost savings 9 US cities for a summer day 1000 kW IT load, Aug 15 ave.

http://www.electricchoic..com/electricity.prices-by-state.php 2010 Industrial rate assumed

| | - | - | | <u> </u> | | | | | |
|--|---------------------|--------------------|--------------|---------------------|-------------|--|--|--|--|
| | Typical data center | DELC based data | Energy | Local cost of | Energy cost | | | | |
| | cooling, kW | center cooling, kW | Savings, kWh | electricity, \$/kWh | savings, \$ | | | | |
| New York City | 500 | 20.7 | 11504 | 0.0973 | 1119.3 | | | | |
| Chicago | 500 | 15.4 | 11631 | 0.075 | 872.3 | | | | |
| San Francisco | 500 | 15.0 | 11640 | 0.1078 | 1254.8 | | | | |
| Raleigh | 500 | 15.6 | 11625 | 0.0613 | 712.6 | | | | |
| Dallas | 500 | 31.5 | 11243 | 0.0658 | 739.8 | | | | |
| Phoenix | 500 | 32.5 | 11220 | 0.0674 | 756.2 | | | | |
| Seattle | 500 | 15.0 | 11640 | 0.0396 | 460.9 | | | | |
| Buffalo | 500 | 16.0 | 11617 | 0.0973 | 1130.3 | | | | |
| Poughkeepsie | 500 | 15.5 | 11627 | 0.0973 | 1131.3 | | | | |
| 50% of IT power DoE 2009 Vision and Roadmap document | | | | | | | | | |

IBM warm water cooled cluster - 2012

Press room > Press releases >

Leibniz Supercomputing Centre Selects IBM Supercomputer Equipped with Next Generation Intel® Xeon® Processors to Support Ultra-challenging Research

Innovative hot-water cooled supercomputer to deliver up to three petaflops of peak performance when online in 2012

Press release

Contact(s) information

Related XML feeds

Garching/Munich/Stuttgart, Germany - 13 Nov 2010: The Leibniz Supercomputing Centre(LRZ) in Garching, Germany has signed a contract with IBM (NYSE: IBM) to develop and build anew general purpose supercomputer with next generation Intel® Yean® processors to supportadvanced scientific research. The system will use iconsume 40 percent less energy than a comparabNamed "SuperMUC", the new system is part of theOn the system is part of theComputer advanced scientific research. The system is part of theNamed "SuperMUC", the new system is part of the

Europe (PRACE) HPC infrastructure for researcher Europe. It will enable LRZ's scientific community to predict outcomes as never before. The supercomp federal government and the state of Bavaria.

- Switch / Storage racks
 - Rear door heat exchangers
- Compute node power consumption reduced ~ 10% due to lower component temperatures and no fans.
- Power Usage Effectiveness P_{Total} / P_{IT}: PUE ~ 1.1
- Heat recovery is enabled by the compute node design.
- Energy Reuse Effectiveness (P_{Total} P_{Reuse}) / P_{IT}: ERE ~ 0.3

IBM warm water cooled servers - 2012

Ref.: I. Meijer, SC11, "Hot Water Cooling for Energy-Hungry Datacenters".

- Heat flux > 90% to water; very low chilled water requirement
- Power advantage over air-cooled node: warm water cooled ~10% (cold water cooled ~15%) due to lower T_{components} and no fans.
- Typical operating conditions: $T_{air} = 25 35^{\circ}C$, $T_{water} = 18 45^{\circ}C$

Thank you Q&A Madhu Iyengar mki@us.ibm.com 845-433-3708

© 2011 IBM Corporation

23